



STEVENS · CRESTO ENGINEERING, INC.

DRAINAGE STUDY

FOR:

OTAY BUSINESS PARK, TM 5505R

(ADDENDUM TO THE APPROVED STUDY FOR OTAY BUSINESS
PARK, TM 5505, DATED MAY 4, 2010)

OTAY MESA, CA

Prepared for:

OTAY BUSINESS PARK, LLC.

4370 La Jolla Village Drive, Suite 640
San Diego, CA 92122

Prepared by:

STEVENS CRESTO ENGINEERING INC.

9665 Chesapeake Drive, Suite 200
San Diego, CA 92123

DATE: 01/31/14
SCE Project: 12009.02

©Stevens Cresto Engineering, Inc. 2014

Env. Log No. PDS2014-ER-9319006WW
Proj. No. PDS2014-GPA-14-004; PDS2014-SPA14-002; PDS2014-TM5505R

TABLE OF CONTENTS

<u>TOPIC</u>	<u>SECTION</u>
PURPOSE OF ADDENDUM	1
VICINITY MAP Otay Business Park, TM 5505R Title Sheet (Reduced) Approved Otay Business Park, TM 5505 Title Sheet (Reduced)	2
PROPOSED CONDITION Exhibit 'A' (11" X 17" Reduction) – Proposed Condition Post-Project Hydrology Detention Pond Routing Calculations	3
CHANNEL CALCULATIONS	4
REFERENCE CALCULATIONS/ EXHIBITS	5
DRAINAGE EXHIBIT Exhibit 'A' – Proposed Condition (Full Size)	6

SECTION 1

PURPOSE OF ADDENDUM

This drainage study has been prepared as an addendum to the approved Drainage Study for: Otay Business Park, TM 5505, dated May 4, 2010. This addendum addresses proposed changes to the project, which are shown on TM 5505R, and include the following: a revised lot and street layout, moving the open drainage channel west, away from the easterly project boundary, and creating a large rough graded pad for future use by the anticipated Point of Entry to the east.

Generally, the proposed TM 5505-R conforms to the findings and conclusions presented in the approved drainage study for TM 5505. The project will honor pre-project watershed basins and discharge points, and will provide peak flow mitigation so run-off flow rates leaving the project site do not exceed pre-project flow rates. The project will utilize two detention ponds, one in the southwest corner of the project and one in the southeast corner, to collect lot runoff and release it at a controlled rate. Detention routing calculations have been updated for the proposed layout and are provided in Section 3. A combination of private and public storm drain systems will collect lot runoff for conveyance to the appropriate detention facility. As proposed with TM 5505, off-site run-on will be routed around or through the project and will not come in contact with project runoff prior to discharge from the detention facilities.

Additionally, Otay Business Park is a Priority Development Project and, as such, is subject to the hydromodification mitigation requirements detailed in the San Diego Countywide Hydromodification Plan, dated March 25, 2011, and required per the Regional Water Quality Control Board Order No. R9-2007-0001, Provision D.1.g (6). The detention facilities proposed at Otay Business Park will be designed to satisfy hydromodification detention requirements, in addition to peak flow detention requirements. Hydromodification calculations are provided within the project SWMP. The two proposed detention facilities will provide adequate hydromodification mitigation for all proposed roads and industrial lots at ultimate buildout. These calculations assume 80% imperviousness for the lots; if any lot proposes impervious surface exceeding 80%, additional hydromodification mitigation will likely be required on-lot. Additionally, water quality measures, such as bioretention, will need to be incorporated on-lot to mitigate for anticipated pollutants generated. All future developments will be subject to a Site Plan review process and will need to provide adequate water quality documentation and calculations as is appropriate at the time of processing.

CONCLUSION

Calculations within this addendum demonstrate that the proposed TM 5505R generally conforms to the findings and calculations presented in the approved Drainage Study for: Otay Business Park, TM 5505, dated May 4, 2010. The project utilizes two detention facilities to provide hydromodification and peak flow mitigation; runoff generated by the project will not exceed pre-project peak flow rates. The following table summarizes pre-project and post-project runoff calculations:

Basin	Pre-Project Condition ¹			Post-Project Condition		
	Drainage Node	Area (acres)	Q ₁₀₀ (cfs)	Area (acres)	Q ₁₀₀ (cfs)	
					Undetained	Detained
A (West)	140	309.2	226.4	317.1	474.7	226.4
B (East)	230	694.1	507.7	713.8	669.2	507.7

¹Taken from the Drainage Study for: Otay Business Park, TM 5505, dated May 4, 2010, see Section 5 for excerpts from study.

Addendum to Drainage Study for :
Otay Business Park, TM 5505, Otay Mesa, CA


DECLARATION OF RESPONSIBLE CHARGE

I hereby declare that I am the Engineer of Work for this project, that I have exercised responsible charge over the design of the project as defined in Section 6703 of the Business and Professions Code, and that the design is consistent with current standards.

I understand that the check of project drawings and specifications by the County of San Diego is confined to a review only and does not relieve me, as Engineer of Work, of my responsibilities for project design.


Mark E. Stevens
R.C.E. 35502

Date




SECTION 2

VICINITY MAP No Scale



COUNTY OF SAN DIEGO TRACT 5505R
TENTATIVE MAP
OTAY BUSINESS PARK



LOT AREAS		LEGEND	
NO.	ACREAGE	DESCRIPTION	SYMBOL
1	2.79	PROPOSED LOT NUMBER	①
2	1.96	SUBDIVISION BOUNDARY	---
3	2.25	INTERNATIONAL BORDER	---
4	2.43	EXISTING CONTOUR	--- 330 ---
5	3.36	PROPOSED LOT LINE	---
6	2.88	PROPOSED RIGHT-OF-WAY	---
7	2.84	PROPOSED RIGHT-OF-WAY SR-11	---
8	1.86	PRIVATE EASEMENT	---
9	2.14	SETBACK	---
10	2.59	FUTURE RIGHT-OF-WAY	---
11	1.72	EXISTING WATER LINE	---
12	2.39	PROPOSED SEWER LINE	---
13	2.75	PROPOSED WATER LINE	---
14	2.73	PROPOSED STORM DRAIN	SD SD
15	3.14	PROPOSED EASEMENT	---
16	2.39	PROPOSED WIND-TYPE HEADWALL	---
17	2.31	PROPOSED CATCH BASIN	---
18	2.29	RIP RAP	---
19	2.61	PROPOSED FORCE MAIN	---
20	2.14	PROPOSED PUMP STATION	---
21	2.70	SLOPE RATIO	1:1 MAX FILL 1.5:1 MAX CUT
22	1.72	PROPOSED CONTOUR	---
23	1.76	DAYLIGHT LINE	---
24	3.36	FLOWAGE	---
25	3.38		
26	3.37		
27	3.34		
28	3.17		
29	3.78		
30	4.06		
31	4.35		
32	6.39		
33	4.29		
34	5.01		
35	36.41		
36	4.68		
TOTAL AREA 141.43 AC.			
ON SITE ROAD AREA 20.22 AC.			
TOTAL PROJECT AREA 161.65 AC.			

SHEET INDEX	
C-1	TENTATIVE MAP
C-2	CROSS SECTIONS & TYPICAL SECTIONS
C-3	PRELIMINARY GRADING PLAN
C-4	PRELIMINARY ROUTE STUDY - AIRWAY ROAD
C-5	PRELIMINARY ROUTE STUDY - SIEMPRE VIVA ROAD
C-6	PRELIMINARY ROUTE STUDY - SIEMPRE VIVA ROAD
C-7	PRELIMINARY ROUTE STUDY - ALTA ROAD
C-8	PRELIMINARY ROUTE STUDY - CHURCO FERNI DRIVE
C-9	SEWER ALIGNMENT
C-10	GRADING PLAN CONFORMANCE NOTES

AREA TABLE	
GROSS ACREAGE WITHIN SUBDIVISION BOUNDARY:	161.65 ACRES
PROPOSED CALTRANS RIGHT-OF-WAY (LOTS 35 & 36)*	41.09 ACRES
PROPOSED ON-SITE PUBLIC ROADWAYS:	20.16 ACRES
PROPOSED ON-SITE DETENTION BASINS "A" & "B" + CHANNEL "C":	8.09 ACRES
TOTAL DEVELOPABLE NET AREA (LOTS 1 THRU 34)**	91.28 ACRES
*AREA OF PROPOSED SIEMPRE VIVA ROAD WITHIN PROPOSED CALTRANS R.O.W. = 2.04 ACRES	
**AREA OF LOT 23 (RESERVED FOR PROPOSED SEWER PUMP STATION) = 1.76 ACRES	

- GENERAL NOTES**
- AREA BREAKDOWN (SEE AREA TABLE ABOVE)
 - TOTAL NUMBER OF LOTS: 36 COMMERCIAL/INDUSTRIAL LOTS INCLUDING: 2 ON-SITE DETENTION BASINS, 1 DRAINAGE CHANNEL EASEMENT AND 1 ON-SITE PUMP STATION LOT. MINIMUM INDUSTRIAL LOT SIZE: 1.72 ACRES
 - EXISTING ZONING - S-88
 - PROPOSED ZONING - S-88
 - GENERAL PLAN REGIONAL CATEGORY: VILLAGE
 - GENERAL PLAN LAND USE DESIGNATION: SPECIFIC PLAN AREA
 - COMMUNITY PLAN OR SUBREGIONAL PLAN: OTAY MESA SUBREGIONAL PLAN, EAST OTAY MESA SPECIFIC PLAN
 - SPECIAL ASSESSMENT ACT PROCEEDINGS - MAY BE REQUESTED FOR THIS PROJECT.
 - PARK LAND DEDICATION NOT REQUIRED IN AN INDUSTRIAL ZONE.
 - STREET LIGHTS WILL BE INSTALLED TO COMPLY WITH THE REQUIREMENTS SPECIFIED BY THE COUNTY STANDARDS.
 - ALL LOTS WITHIN THIS SUBDIVISION HAVE A MINIMUM OF 100 SQUARE FEET OF SOLAR ACCESS FOR EACH FUTURE DWELLING/COMMERCIAL/INDUSTRIAL UNIT ALLOWED BY THIS SUBDIVISION.
 - SOURCE OF TOPOGRAPHY: PREPARED BY PHOTO GEODETIC CORPORATION. DATE OF PHOTOGRAPHY: OCTOBER 15, 2009
 - DISTRICTS / UTILITY SERVICE PROVIDERS:
SEWER - SAN DIEGO COUNTY SANITATION DISTRICT
WATER - OTAY WATER DISTRICT
GAS & ELECTRIC - SDGE
TELEPHONE - AT&T
FIRE - SAN DIEGO RURAL FIRE PROTECTION DISTRICT
STREET LIGHTING - COUNTY OF SAN DIEGO
 - ALL PROPOSED UTILITIES TO BE UNDERGROUND EXCEPT WATER TREATMENT SWALES.
 - ALL ON-SITE STREETS WILL BE PUBLIC.
 - IMPROVEMENTS, EASEMENTS AND DEDICATIONS WILL COMPLY WITH THE REQUIREMENTS SPECIFIED IN THE COUNTY STANDARDS.
 - ALL EXISTING EASEMENTS NOT REMAINING IN USE SHALL BE VACATED PRIOR TO RECORDATION OF THE FINAL MAP(S) SUBJECT TO THE SATISFACTION OF THE DIRECTOR OF PUBLIC WORKS.
 - STORM DRAIN DETENTIONS SHALL BE PROVIDED IN ACCORDANCE WITH THE REQUIREMENTS OF THE EAST OTAY MESA SPECIFIC PLAN. THIS DETENTION WILL BE ACCOMPLISHED THROUGH UTILIZATION OF 2 DETENTION BASINS TO SERVE THE OVERALL PROJECT.
 - LANDMARK COORDINATES: 138-1785
 - THIS PLAN IS PROVIDED TO ALLOW FOR FULL AND ADEQUATE DISCRETIONARY REVIEW OF A PROPOSED DEVELOPMENT PROJECT. THE PROPERTY OWNER ACKNOWLEDGES THAT ACCEPTANCE OR APPROVAL OF THIS PLAN DOES NOT CONSTITUTE AN APPROVAL TO PERFORM ANY GRADING SHOWN HEREON, AND AGREES TO OBTAIN VALID GRADING PERMITS BEFORE COMMENCING SUCH ACTIVITY.
 - THIS PROJECT IS A MULTI-UNIT SUBDIVISION. MULTIPLE FINAL MAPS MAY BE FILED PURSUANT TO SECTION 66456.1 OF THE SUBDIVISION MAP ACT
 - PRIOR TO THE APPROVAL OF ANY SITE PLAN FOR ANY DEVELOPMENT PROPOSAL WITHIN THE NOISE PROTECTION EASEMENT, THE APPLICANT SHALL:
M-N-2: THE PERMIT COMPLIANCE ENGINEER SHALL ENSURE THAT ON-SITE GRADING OPERATIONS DO NOT OCCUR WITHIN 225 FEET OF ANY PROPERTY LINE THAT ADJUTS PROPERTIES WHERE ACTIVE GRADING ACTIVITIES ARE OCCURRING. ON-SITE GRADING ACTIVITIES ADJUTING TO THE PROPERTY LINE MAY OCCUR IF GRADING ACTIVITIES FOR ADJACENT PROPERTIES ARE OCCURRING AT A MINIMUM DISTANCE OF 225 FEET FROM THE SHARED PROPERTY LINE. THE PERMIT COMPLIANCE ENGINEER (AS DEFINED IN SECTION 87.420 OF THE COUNTY GRADING ORDINANCE) SHALL DEMONSTRATE COMPLIANCE WITH THIS REQUIREMENT IN THE REGULAR REPORTS REQUIRED PURSUANT TO SECTION 87.420(A) OF THE COUNTY'S GRADING ORDINANCE. THE REGULAR REPORTS SHALL IDENTIFY ANY DAYS WHERE GRADING ACTIVITIES WERE RESTRICTED ON-SITE OR ON ADJACENT PROPERTIES IN ORDER TO ENSURE A MINIMUM DISTANCE OF 225 FEET BETWEEN GRADING ACTIVITIES.

OWNER/SUBDIVIDER
OTAY BUSINESS PARK
4370 LA JOLLA VILLAGE DRIVE, SUITE 640
SAN DIEGO, CA 92122
PHONE: 858-535-9047
FAX: 858-535-9100

BY: RICARDO JINICH DATE: _____

ENGINEER OF WORK
MARK E. STEVENS
R.C.E. 35502


DATE: _____

REVISIONS

NO.	DESCRIPTION

DATE: FEBRUARY 2014
SCALE: AS SHOWN
DRAWN: SCE
JOB: 12009.02
SHEET: C-1
1 of 10 Sheets

- EASEMENTS / EXCEPTIONS / RESTRICTIONS**
- WITH THE APPROVAL OF THE FINAL MAP(S), FOR THE DRAINAGE TO MEXICO EASEMENTS SHALL BE DEDICATED TO THE COUNTY OF SAN DIEGO OVER DETENTION BASINS, APPURTENANT STRUCTURES AND ACCESS ROUTES (AND ROUTES NECESSARY TO MAINTAIN THE FOREGOING) TO A COUNTY MAINTAINED ROAD. THIS REQUIRES HYDROLOGIC AND HYDRAULIC REPORTS TO ENSURE APPROPRIATE PRIVATE STORMWATER DETENTION FACILITIES SUCH THAT PEAK STORMWATER FLOWS FROM THE ENTIRE SITE REMAIN THE SAME AS BEFORE THE PROJECT WAS DEVELOPED. ALL OF THE FOREGOING SHALL BE TO THE SATISFACTION OF THE DIRECTOR OF PUBLIC WORKS.
- SEE PRELIMINARY TITLE REPORT BY STEWART TITLE OF CALIFORNIA, INC., ORDER NO. 01-025783, DATED NOVEMBER 7, 2005. ITEMS LISTED BELOW ARE SHOWN IN THE PRELIMINARY TITLE REPORT WHICH EFFECTS ASSESSOR'S PARCEL NO. 648-070-21. PLOTTABLE ITEMS ARE DENOTED THUS: X WITH LOCATIONS KEYS THE SAME HEREON.
- AN EASEMENT TO OTAY MUNICIPAL WATER DISTRICT FOR THE CONSTRUCTION AND MAINTENANCE OF PIPELINES, RECORDED JUNE 5, 1968 AS FILE NO. 93912, OF OFFICIAL RECORDS.
 - AN EASEMENT TO OTAY MUNICIPAL WATER DISTRICT FOR THE CONSTRUCTION AND MAINTENANCE OF PIPELINES, RECORDED JANUARY 6, 1970 AS FILE NO. 2033, OF OFFICIAL RECORDS.
 - AN EASEMENT TO OTAY MUNICIPAL WATER DISTRICT FOR THE CONSTRUCTION AND MAINTENANCE OF PIPELINES, RECORDED FEBRUARY 26, 1974 AS FILE NO. 74-051081, OF OFFICIAL RECORDS.
 - THE EFFECT OF A DOCUMENT OF JOINT USE BETWEEN SAN DIEGO GAS & ELECTRIC AND OTAY WATER DISTRICT, RECORDED JANUARY 11, 1990, AS FILE NO. 1999-003773, OF OFFICIAL RECORDS, UNPLOTTABLE.
 - 40' EASEMENT TO SAN DIEGO GAS & ELECTRIC FOR PUBLIC UTILITIES, RECORDED MARCH 24, 1999, AS FILE NO. 1999-0191043, OF OFFICIAL RECORDS.
 - EXISTING 24" ADP TIAJANA WATER MAIN PER O.M.W.D. DWG. 16-3-7
 - EXISTING 12" WATER MAIN PER O.M.W.D. DWG. 16-7-7
 - EXISTING 16" WATER MAIN PER O.M.W.D. DWG. 16-7-7
 - 30' EGRESS/INGRESS IN BENEFIT OF SUBJECT PROPERTY (SEE LEGAL DESCRIPTION, PARCEL 2)
 - A 20' SEWER ACCESS AND MAINTENANCE EASEMENT TO COUNTY OF SAN DIEGO.
 - DESIGNATED BIOLOGICAL OPEN SPACE SHALL COMPLY WITH COVENANTS AND RESTRICTIONS IDENTIFIED IN THE OTAY BUSINESS PARK EIR AND BIOLOGICAL REPORT.
 - UNITED BUILDING ZONE. ALL LOTS AFFECTED SHALL COMPLY WITH BUILDING RESTRICTIONS AS IDENTIFIED IN THE OTAY BUSINESS PARK ENVIRONMENTAL IMPACT REPORT AND FIRE PROTECTION PLAN.



NOTE: TRENCH BACKFILL SHALL CONSIST OF NATIVE MATERIALS, APPROVED BY THE SOILS ENGINEER PRIOR TO PLACEMENT. OPEN-GRADED, HIGHLY PERMEABLE MATERIAL SHALL NOT BE USED AS BACKFILL.

OWP RISER, HOT-DIPPED GALVANIZED 12-GAUGE, 2-2/3 INCH X 1/2 INCH CORRUGATIONS. DIAMETER PER PLANS. CUT FIVE HORIZONTAL SLOTS IN 1/4 INCH X 10 INCHES (EQUALLY SPACED AROUND CIRCUMFERENCE). FIRST ROW TO BE 4 INCHES BELOW UNIVERSAL BAND COUPLER. SECOND ROW TO BE STAGGERED AT 5-1/3 INCHES BELOW FIRST ROW. CONTINUE STAGGERED ROWS UNTIL 24 INCHES ABOVE SOFFET OF PRIVATE STORM DRAIN PIPE.

MAINTENANCE
SEDIMENT SHALL BE REMOVED WHENEVER STORAGE CAPACITY (AT DEPTH 1") HAS BEEN ACHIEVED. SEDIMENT SHALL BE DISPOSED OF IN SUCH A MANNER THAT WILL PREVENT ITS RETURN TO THE DESILTING BASIN OR MOVEMENT INTO DOWNSTREAM AREAS DURING SUBSEQUENT RUNOFF. THE DESILTING BASINS ARE PRIVATE FACILITIES, AND THE COUNTY WILL NOT BE RESPONSIBLE FOR THEIR MAINTENANCE.

PVT. TEMPORARY EROSION CONTROL DESILTING BASIN
NO SCALE

ASSESSOR'S PARCEL NUMBER	
648-070-21	
TAX RATE AREA	
84035	
EXISTING SLOPE ANALYSIS TABLE	
0-15% SLOPES	158.83 AC.
15-25% SLOPES	1.32 AC.
25-50% SLOPES	1.27 AC.
50% OR GREATER SLOPES	0.18 AC.
TOTAL	161.60 AC.

NOTE: GRADING QUANTITIES ARE ESTIMATED FOR PERMIT PURPOSES ONLY AND ARE NOT INTENDED TO BE USED AS FINAL PAY QUANTITIES.

BASIS OF BEARING
THE BASIS OF BEARINGS FOR THIS SURVEY IS THE MAD 83, ZONE 6 GRID BEARING BETWEEN CITY OF SAN DIEGO CONTROL MONUMENTS 1494 AND 1496 AS SHOWN ON RECORD OF SURVEY 14492 BEARING: NORTH 44°35'23" WEST


LEGAL DESCRIPTION
PARCEL 1:
THE SOUTHEAST QUARTER OF SECTION 31, TOWNSHIP 18 SOUTH, RANGE 1 EAST, SAN BERNARDINO BASE AND MERIDIAN, IN THE COUNTY OF SAN DIEGO, STATE OF CALIFORNIA, ACCORDING TO THE OFFICIAL PLAT THEREOF.

EXCEPTION THEREFROM THAT PORTION CONVEYED TO UNITED STATES OF AMERICA, IMMIGRATION AND NATURALIZATION SERVICE BE DEED RECORDED APRIL 7, 2000, AS FILE NO. 2000-0177412, OFFICIAL RECORDS.

PARCEL 2:
AN EASEMENT FOR INGRESS AND EGRESS OVER THE EASTERLY 30 FEET OF THE WEST ONE-HALF OF SECTION 31, TOWNSHIP 18 SOUTH, RANGE 1 EAST, SAN BERNARDINO BASE AND MERIDIAN, IN THE COUNTY OF SAN DIEGO, STATE OF CALIFORNIA, ACCORDING TO THE OFFICIAL PLAT THEREOF.

ZONING APN 648-070-21	
ZONE	588
USE REGULATIONS	---
ANIMAL REGULATIONS	---
DENSITY	---
LOT SIZE	30,000
BUILDING TYPE	---
MAX. FLOOR AREA	---
FLOOR AREA RATIO	0.40
HEIGHT	R
LOT COVERAGE	0.40
SETBACK	V
OPEN SPACE	---
SPECIAL AREA REGULATIONS	B, P or G

COUNTY OF SAN DIEGO TRACT 5505
REPLACEMENT TENTATIVE MAP
OTAY BUSINESS PARK



LOT AREAS	
NO.	NET ACREAGE
1	1.92
2	1.91
3	1.90
4	1.78
5	1.69
6	1.91
7	1.89
8	1.60
9	1.56
10	1.59
11	1.58
12	1.92
13	1.60
14	1.60
15	1.28
16	1.46
17	1.49
18	2.00
19	1.86
20	2.80
21	2.29
22	1.33
23	1.95
24	1.95
25	1.35
26	0.94
27	1.74
28	1.44
29	1.68
30	1.06
31	1.43
32	2.07
33	2.01
34	1.40
35	2.89
36	0.83
37	1.72
38	1.00
39	1.91
40	1.86
41	1.69
42	1.98
43	1.13
44	1.15
45	0.91
46	1.13
47	5.05
48	3.40
49	3.44
50	3.36
51	1.53
52	2.67
53	2.32
54	2.00
55	2.12
56	2.67
57	1.77
58	4.65
59	4.27

LEGEND	
DESCRIPTION	SYMBOL
PROPOSED LOT NUMBER	1
SUBDIVISION BOUNDARY	---
INTERNATIONAL BORDER	---
EXISTING CONTOUR	---
PROPOSED LOT LINE	---
PROPOSED RIGHT-OF-WAY	---
PROPOSED RIGHT-OF-WAY SR-11	---
EXISTING WATER LINE	---
PROPOSED SEWER LINE	---
PROPOSED WATER LINE	---
PROPOSED RECLAIMED WATER LINE	---
PROPOSED STORM DRAIN	---
PROPOSED STORM DRAIN SIZE	---
PROPOSED EASEMENT	---
PROPOSED WING-TYPE HEADWALL	---
PROPOSED CATCH BASIN	---
PROPOSED FORCE MAIN	---
PROPOSED PUMP STATION	---
SLOPE RATIO	2:1 MAX FULL 1.5:1 MAX CUT
PROPOSED STREET LIGHT	---
PHASING LINE	---
PROPOSED CONTOUR	---
RIP RAP	---
DAYLIGHT LINE	---
DESILT BASINS	---
VEGETATED SWALE (PRIVATELY MAINTAINED)	---
ACCESS DRIVEWAY EXCEPTIONS (APPROXIMATE LOCATIONS)	---
BIOLOGICAL OPEN SPACE (SEE NOTE THIS SHEET)	---

LOT / UNIT TABLE	
LOTS 1-20 UNIT NO. 1	116.62 AC.
LOTS 21-37 UNIT NO. 2	4.85 AC.
LOTS 38-50 UNIT NO. 3	1.78 AC.
LOTS 51-59 UNIT NO. 4	13.02 AC.
ANCILLARY AREA	19.63 AC.
ON-SITE ROAD AREA	25.35 AC.
TOTAL PROJECT AREA	161.6 AC.

SHEET INDEX	
TITLE SHEET	C-1
CROSS SECTIONS AND TYPICAL SECTIONS	C-2
SITE PLAN - NORTH HALF	C-3
SITE PLAN - SOUTH HALF	C-4
GRADING TITLE SHEET	C-5
GRADING PLAN - NORTH HALF	C-6
GRADING PLAN - SOUTH HALF	C-7
SLOPE ANALYSIS	C-8
PRELIMINARY ROUTE ALIGNMENT STUDY (PLAN AND PROFILE)	C-9 THRU C-15
OFFSITE IMPROVEMENTS (PLAN AND PROFILE)	C-16 THRU C-17
SEWER ALIGNMENT	C-18
OFFSITE EASEMENTS AND DEDICATIONS	C-19
GRADING PLAN CONFORMANCE NOTES	C-20

- GENERAL NOTES:**
- GROSS ACRES WITHIN SUBDIVISION BOUNDARY: 161.62 ACRES
GROSS DEVELOPABLE LOT AREA: 116.4 ACRES
PROPOSED ON-SITE STREETS: 25.4 ACRES
PROPOSED ON-SITE DETENTION BASINS: 6.61 ACRES
PROPOSED ON-SITE DRAINAGE CHANNEL: 13.0 ACRES
PROPOSED PUMP STATION: 1.0 ACRES
 - TOTAL NUMBER OF LOTS: 59 COMMERCIAL/INDUSTRIAL LOTS
2 ON-SITE DETENTION BASINS, 1 ON-SITE PUMP STATION
MINIMUM INDUSTRIAL LOT SIZE IS 0.90 ACRES
 - EXISTING ZONING - S-88
 - PROPOSED ZONING - S-88
 - GENERAL PLAN REGIONAL CATEGORY: VILLAGE
 - GENERAL PLAN LAND USE DESIGNATION: SPECIFIC PLAN AREA
 - COMMUNITY PLAN OR SUBREGIONAL PLAN: OTAY SUBREGIONAL PLAN, EAST OTAY MESA SPECIFIC PLAN
 - SPECIAL ASSESSMENT ACT PROCEEDINGS - MAY BE REQUESTED FOR THIS PROJECT.
 - PARK LAND DEDICATION NOT REQUIRED IN AN INDUSTRIAL ZONE.
 - STREET LIGHTS WILL BE INSTALLED TO COMPLY WITH THE REQUIREMENTS SPECIFIED BY THE COUNTY STANDARDS.
 - ALL LOTS WITHIN THIS SUBDIVISION HAVE A MINIMUM OF 100 SQUARE FEET OF SOLAR ACCESS FOR EACH FUTURE DWELLING/COMMERCIAL/INDUSTRIAL UNIT ALLOWED BY THIS SUBDIVISION.
 - SOURCE OF TOPOGRAPHY: PREPARED BY PHOTO GEODETIC CORPORATION, TOPOGRAPHIC INFORMATION FLOWN ON OCTOBER 15, 2009
 - DISTRICTS: SEWER - SAN DIEGO COUNTY SANITATION DISTRICT
WATER - OTAY WATER DISTRICT
GAS & ELECTRIC - SDG&E
TELEPHONE - AT&T
FIRE - SAN DIEGO RURAL FIRE PROTECTION DISTRICT
STREET LIGHTING - COUNTY OF SAN DIEGO
 - ALL PROPOSED UTILITIES TO BE UNDERGROUND EXCEPT WATER TREATMENT SWALES.
 - ALL ON-SITE STREETS WILL BE PUBLIC.
 - IMPROVEMENTS, EASEMENTS AND DEDICATIONS WILL COMPLY WITH THE REQUIREMENTS SPECIFIED IN THE COUNTY STANDARDS.
 - ALL EXISTING EASEMENTS NOT REMAINING IN USE SHALL BE VACATED PRIOR TO RECORDATION OF THE FINAL MAP(S) SUBJECT TO THE SATISFACTION OF THE DIRECTOR OF PUBLIC WORKS.
 - STORM DRAIN DETENTIONS SHALL BE PROVIDED BY ACCORDANCE WITH THE REQUIREMENTS OF THE EAST OTAY MESA SPECIFIC PLAN. THIS DETENTION WILL BE ACCOMPLISHED THROUGH UTILIZATION OF 2 DETENTION BASINS TO SERVE THE OVERALL PROJECT.
 - LANBERT COORDINATES: 138-1785
 - THIS PLAN IS PROVIDED TO ALLOW FOR FULL AND ADEQUATE DISCRETIONARY REVIEW OF A PROPOSED DEVELOPMENT PROJECT. THE PROPERTY OWNER ACKNOWLEDGES THAT ACCEPTANCE OR APPROVAL OF THIS PLAN DOES NOT CONSTITUTE AN APPROVAL TO PERFORM ANY GRADING SHOWN HEREON, AND AGREES TO OBTAIN VALID GRADING PERMITS BEFORE COMMENCING SUCH ACTIVITY.
 - THIS PROJECT IS A MULTI-UNIT SUBDIVISION. MULTIPLE FINAL MAPS MAY BE FILED PURSUANT TO SECTION 66456.1 OF THE SUBDIVISION MAP ACT
 - PRIOR TO THE APPROVAL OF ANY SITE PLAN FOR ANY DEVELOPMENT PROPOSAL WITHIN THE NOISE PROTECTION EASEMENT, THE APPLICANT SHALL:
M-N-2: THE PERMIT COMPLIANCE ENGINEER SHALL ENSURE THAT ON-SITE GRADING OPERATIONS DO NOT OCCUR WITHIN 225 FEET OF ANY PROPERTY LINE THAT ADJUTS PROPERTIES WHERE ACTIVE GRADING ACTIVITIES ARE OCCURRING. ON-SITE GRADING ACTIVITIES ADJUTS TO THE PROPERTY LINE MAY OCCUR IF GRADING ACTIVITIES FOR ADJACENT PROPERTIES ARE OCCURRING AT A MINIMUM DISTANCE OF 225 FEET FROM THE SHARED PROPERTY LINE. THE PERMIT COMPLIANCE ENGINEER (AS DEFINED IN SECTION 67420 OF THE COUNTY GRADING ORDINANCE) SHALL DEMONSTRATE COMPLIANCE WITH THIS REQUIREMENT IN THE REGULAR REPORTS REQUIRED PURSUANT TO SECTION 67420(c) OF THE COUNTY GRADING ORDINANCE. THE REGULAR REPORTS SHALL IDENTIFY ANY DAYS WHERE GRADING ACTIVITIES WERE RESTRICTED ON-SITE OR ON ADJACENT PROPERTIES IN ORDER TO ENSURE A MINIMUM DISTANCE OF 225 FEET BETWEEN GRADING ACTIVITIES.

ASSASSIN'S PARCEL MAP
648-070-21
TAX RATE AREA
84035

ZONING APN 648-070-21	
USE REGULATIONS	S88
ANNUAL REGULATIONS	
DENSITY	---
LOT SIZE	30,000
BUILDING TYPE	W
MAX FLOOR AREA	---
FLOOR AREA RATIO	0.40
HEIGHT	---
LOT COVERAGE	0.40
SETBACK	---
OPEN SPACE	---
SPECIAL AREA REGULATIONS	B, P or G

LEGAL DESCRIPTION
PARCEL 1:
THE SOUTHEAST QUARTER OF SECTION 31, TOWNSHIP 18 SOUTH, RANGE 1 EAST, SAN BERNARDINO BASE AND MERIDIAN, IN THE COUNTY OF SAN DIEGO, STATE OF CALIFORNIA, ACCORDING TO THE OFFICIAL PLAT THEREOF.
EXCEPTION THEREFROM THAT PORTION CONVEYED TO UNITED STATES OF AMERICA, IMMIGRATION AND NATURALIZATION SERVICE BE DEED RECORDED APRIL 7, 2000, AS FILE NO. 2000-0177412, OFFICIAL RECORDS.
PARCEL 2:
AN EASEMENT FOR INGRESS AND EGRESS OVER THE EASTERLY 30 FEET OF THE WEST ONE-HALF OF SECTION 31, TOWNSHIP 18 SOUTH, RANGE 1 EAST, SAN BERNARDINO BASE AND MERIDIAN, IN THE COUNTY OF SAN DIEGO, STATE OF CALIFORNIA, ACCORDING TO THE OFFICIAL PLAT THEREOF.

- EASEMENTS / EXCEPTIONS / RESTRICTIONS**
- WITH THE APPROVAL OF THE FINAL MAP(S), FOR THE DRAINAGE TO MEXICO EASEMENTS SHALL BE DEDICATED TO THE COUNTY OF SAN DIEGO OVER DETENTION BASINS, APPURTENANT STRUCTURES AND ACCESS ROUTES (SAID ROUTES NECESSARY TO MAINTAIN THE FOREGOING) TO A COUNTY MAINTAINED ROAD. THIS REQUIREMENT HYDROLOGIC AND HYDRAULIC REPORTS TO ENSURE APPROPRIATE PRIVATE STORMWATER DETENTION FACILITIES SUCH THAT PEAK STORMWATER FLOWS FROM THE ENTIRE SITE REMAIN THE SAME AS BEFORE THE PROJECT WAS DEVELOPED. ALL OF THE FOREGOING SHALL BE TO THE SATISFACTION OF THE DIRECTOR OF PUBLIC WORKS.
- SEE PRELIMINARY TITLE REPORT BY STEWART TITLE OF CALIFORNIA, INC., ORDER NO. 01-0251783, DATED NOVEMBER 7, 2005. ITEMS LISTED BELOW ARE SHOWN IN THE PRELIMINARY TITLE REPORT WHICH EFFECTS ASSESSOR'S PARCELS NO. 648-070-21. PLOTTABLE ITEMS ARE DENOTED THUS: X WITH LOCATIONS KEYED THE SAME HEREON.
- AN EASEMENT TO OTAY MUNICIPAL WATER DISTRICT FOR THE CONSTRUCTION AND MAINTENANCE OF PIPELINES, RECORDED JUNE 5, 1968 AS FILE NO. 93912, OF OFFICIAL RECORDS.
 - AN EASEMENT TO OTAY MUNICIPAL WATER DISTRICT FOR THE CONSTRUCTION AND MAINTENANCE OF PIPELINES, RECORDED JANUARY 6, 1970 AS FILE NO. 2033, OF OFFICIAL RECORDS.
 - AN EASEMENT TO OTAY MUNICIPAL WATER DISTRICT FOR THE CONSTRUCTION AND MAINTENANCE OF PIPELINES, RECORDED FEBRUARY 26, 1974 AS FILE NO. 74-051081, OF OFFICIAL RECORDS.
 - THE EFFECT OF A DOCUMENT OF JOINT USE BETWEEN SAN DIEGO GAS & ELECTRIC AND OTAY WATER DISTRICT, RECORDED JANUARY 11, 1999, AS FILE NO. 1999-0036773, OF OFFICIAL RECORDS, UNPLOTTABLE.
 - EXISTING 24" ACP TAJANA WATER MAIN PER O.M.W.D. DWG. 16-3-7
 - EXISTING 12" WATER MAIN PER O.M.W.D. DWG 16-7-7
 - EXISTING 16" WATER MAIN PER O.M.W.D. DWG 16-7-7
 - 30' INGRESS/EGRESS IN BENEFIT OF SUBJECT PROPERTY (SEE LEGAL DESCRIPTION, PARCEL 2)

- EASEMENTS / EXCEPTIONS / RESTRICTIONS (CONTINUED)**
- A 20' SEWER ACCESS AND MAINTENANCE EASEMENT TO COUNTY OF SAN DIEGO.
 - DESIGNATED BIOLOGICAL OPEN SPACE SHALL COMPLY WITH COVENANTS AND RESTRICTIONS IDENTIFIED IN THE OTAY BUSINESS PARK ENVIRONMENTAL IMPACT REPORT AND FIRE PROTECTION PLAN.
 - LIMITED BUILDING ZONE: ALL LOTS AFFECTED SHALL COMPLY WITH BUILDING RESTRICTIONS AS IDENTIFIED IN THE OTAY BUSINESS PARK ENVIRONMENTAL IMPACT REPORT AND FIRE PROTECTION PLAN.
- GRADING QUANTITIES**
GRADED AREA 10160 ACRES
CUT QUANTITIES 1,200,000 CYD
FILL QUANTITIES 1,200,000 CYD
IMPORT/EXPORT 0 CYD
- NOTE: GRADING QUANTITIES ARE ESTIMATED FOR PERMIT PURPOSES ONLY AND ARE NOT INTENDED TO BE USED AS FINAL PAY QUANTITIES.
- BASE OF BEARING**
THE BASES OF BEARING FOR THIS SURVEY IS THE NAD 83 ZONE 6 GRID BEARING BETWEEN CITY OF SAN DIEGO CONTROL MONUMENTS 1494 AND 1496 AS SHOWN ON RECORD OF SURVEY 14492 BEARING: NORTH 44°35'23" WEST
- OWNER/SUBOWNER**
OTAY BUSINESS PARK
4370 LA JOLLA VILLAGE DRIVE, SUITE 640
SAN DIEGO, CA 92122
PHONE: (619) 536-9047
FAX: (619) 536-9107
- APPROVED** 10/14/2011
RICARDO JINCH DATE

REVISIONS

NO.	DESCRIPTION	DATE
1	ISSUED FOR PERMITTING	7/1/2008

TITLE SHEET

SAN DIEGO
OTAY BUSINESS PARK
COUNTY OF SAN DIEGO, CALIFORNIA

*** APPROVED TM ***

SDC DPLU RCVD 10-17-11
TM5505

Date: JULY 2008
Scale: AS SHOWN
Drawn: SEB
Job: 066529000
Sheet: C-1
1 of 20 Sheets

Kimley-Horn and Associates, Inc.
2010 KIMLEY-HORN AND ASSOCIATES, INC.
Engineering, Planning, and Environmental Consultants
400 B Street, Suite 600
San Diego, CA 92101
Tel: (619) 234-9411 Fax: (619) 234-9433

SECTION 3

PROPOSED CONDITION

PROJECT HYDROLOGY

Consistent with the approved Drainage Study for: Otay Business Park, TM 5505, this report analyzes runoff generated from two distinct watersheds, labeled Basins "A" and "B" within this study. Those basins are generally referred to as "west" (Basin A) and "east" (Basin B) within the approved study. A third basin, along the eastern project boundary, is also analyzed in that study. As with TM5505, the replacement TM will incorporate approximately 15.6 acres of the basin into Basin B. Since the only change to that watershed basin is a reduction in area consistent with the approved study for TM5505, no further analysis is provided.

The proposed project will generally maintain pre-project watershed areas and discharge locations. Pre-project hydrologic calculations are taken from the approved study for TM5505 and are provided in Section 5 for reference; for the pre-project condition, see the reduced copy of Exhibit B – Existing Condition also in that section. The proposed industrial land use at the project is consistent with the approved TM, though the number of lots has been reduced to allow for a large rough graded pad along the eastern boundary. It is anticipated that this pad will be utilized by the future Point of Entry east of the project.

Post-Project Runoff Coefficient: In the post-project condition, the approved study utilized a runoff coefficient of 0.87 (95% imperviousness) for the future industrial lots. This value is inconsistent with the approved Hydromodification Management Plan for the project, which assumed 70% imperviousness, and is unrealistic given that the future lots will need to incorporate Low Impact Development measures, such as bioretention, for storm water treatment. Recent experience in the area has found that 80% imperviousness is a reasonable value to provide LID storm water treatment and have adequate impervious surface to support industrial land use. As such, the project proposes a maximum on-lot imperviousness of 80% and, per the County of San Diego Hydrology Manual, uses a runoff coefficient of 0.79. Should any future developments propose impervious surface exceeding 80%, they will likely need to provide additional peak flow and hydromodification mitigation on-site.

Post-Project Basin A: the project proposes to collect and convey runoff within a combination of private and public storm drain systems for conveyance to Detention Pond A in the southwest corner of the project. Offsite run-on from the north will be collected in a bypass storm drain system which will run down Alta Road and discharge at the southwest corner of the project, near the outlet for Detention Pond A. Given that the size and configuration of Basin A is generally consistent with the approved TM, this study utilizes the on-site time of concentration of 12 minutes calculated in the approved study for TM5505. Basin "A" is comprised of 317.1 acres and generates a peak runoff rate of approximately 474.7 cfs during the 100-year storm event. The area of the Basin increases slightly from the pre-project condition since the project will construct offsite portions of Airway Road and Siempre Viva Road, to the west, and runoff generated by those roads requires mitigation. Runoff from the roads will be collected and conveyed, within the onsite storm drain system, to Detention Pond A.

Post-Project Basin B: the project proposes to collect and convey runoff within a combination of private and public storm drain systems for conveyance to Detention Pond B in the southeast corner of the project. Offsite run-on from the north will be conveyed through the

project within an open channel, see Section 4 for additional channel calculations. The channel outlets at the southern boundary, near the outlet for Detention Pond B. Given that the configuration of Basin B is generally consistent with the approved TM, this study utilizes the on-site time of concentration of 8 minutes calculated in the approved study for TM5505. Basin "B" is comprised of 713.8 acres and generates a peak runoff rate of approximately 507.7 cfs during the 100-year storm event. The area of the Basin increases from the pre-project condition since the area east of the open channel will be graded as one large pad for use by the future Point of Entry to the east, and it incorporates approximately 15.6 acres of the adjacent watershed basin, consistent with TM5505. Runoff generated by this pad is collected and discharged directly to the open channel. Any future development on the pad will need to provide on-lot peak runoff and hydromodification mitigation; Detention Pond B is not sized to provide mitigation for that lot. Given that the proposed project will stabilize the pad with hydroseed and substantial erosion control, significantly slowing runoff and mimicking pre-project conditions, a runoff coefficient of 0.35 is applied to the pad for calculations in this study.

DETENTION CALCULATIONS

Calculations within this section utilize Hydraflow Hydrographs 2007 to route post-project 100-year peak flow rates through the proposed detention facilities. The two detention facilities are sized, and outlet configurations designed, to provide adequate hydromodification mitigation per the calculations provided in the project SWMP. Calculations demonstrate that peak outflow from those basins, combined with offsite run-on, will not exceed pre-project discharge rates.

Drawdown Calculations: The detention routing calculations in this section find that the two detention ponds will exceed the maximum allowable drawdown time of 96 hours. As currently designed, the facilities will require approximately 10 days to drawdown. This extended timeframe is consistent with, and slightly improves upon, the calculations provided in the approved study for TM5505. The approved Hydromodification Management Plan for the TM5505 provides a Vector Control Plan to address the drawdown issues. Though the project may still use the Vector Control Plan, it is anticipated that additional calculations will be performed at final engineering to reduce the drawdown time and potentially eliminate the need for the plan. Recent experience in the San Diego County area has found success in using SWMM continuous modeling software, as approved in the Final Hydromodification Management Plan, to reduce detention volumes, increase outlet orifice sizes, and decrease drawdown times, when compared to the results of the BMP Sizing Calculator. Due to the time intensive nature of the SWMM modeling calculations, however, they are generally not appropriate or necessary for use at discretionary level processing and will be performed at final engineering, if deemed necessary.

Addendum to Drainage Study for :
Otay Business Park, TM 5505, Otay Mesa, CA

POST-PROJECT HYDROLOGY



LEGEND

- PROPOSED GROUND CONTOURS 360
- EXISTING GROUND CONTOURS 360 INDEX 360 INTERMEDIATE
- DRAINAGE BASIN DESIGNATOR
- A 0.57 - BASIN DESIGNATION (ALPHA CHARACTERS DESIGNATE REGIONAL RUNOFF AREAS)
- BASIN AREA (Acres)
- DRAINAGE BASIN BOUNDARY
- PROPERTY LINE
- STORM DRAIN PIPE
- STORM DRAIN CLEANOUT
- STORM DRAIN CATCH BASIN
- STORM DRAIN CURB INLET
- PROPOSED STORM WATER COLLECTION BASIN & RISER
- PROPOSED OPEN DRAINAGE CHANNEL
- PROPOSED HEADWALL/ENERGY DISSIPATOR
- PROPOSED BROW DITCH

NODE 140
Q100=474.7 CFS (UNDETAINED)
Q100=226.4 CFS MAX. (DETAINED)

DETENTION POND "A"

DETENTION POND "B"

NODE 230
Q100=669.2 CFS (UNDETAINED)
Q100=507.7 CFS MAX. (DETAINED)



STEVENS-CRESTO ENGINEERING, INC.
CIVIL ENGINEERS - PLANNERS - LAND SURVEYORS
9445 CUESA DRIVE
SUITE 200
SAN DIEGO, CA 92123-1352
PHONE: 619.494.5540
FAX: 619.494.5541
www.sceengr.com

OTAY BUSINESS PARK
TRACT 5505R
SAN DIEGO, CALIFORNIA

EXHIBIT "A"
PROPOSED CONDITION

*REDUCED - SEE FULL SIZE IN SECTION 6 *

DATE: 01/31/14
SCE NO. 12009.02
SHEET
A
1 OF 1 SHEET

OTAY BUSINESS PARK - PROPOSED CONDITION

POST-PROJECT HYDROLOGY - BASIN A (WEST)

(Rational Method Procedure)

Otay Mesa, CA

DESIGN STORM

100 YR

RUN:

1/30/14 4:27 PM

P6= 3.0

BASIN INFORMATION									
DRAINAGE BASIN	AREA ac.	RUNOFF COEFF	T _c min	C x A	I ₁₀₀ in/hr	Undetained Q ₁₀₀ cfs	Approx. Detained Q ₁₀₀ cfs	REMARKS	TRIBUTARY TO
A1	2.80	0.79	12.0	2.21	4.49	9.9	1.9	Lot (80% Impervious Max.)	POND A
A2	2.40	0.79	12.0	1.90	4.49	8.5	1.6	Lot (80% Impervious Max.)	POND A
A3	3.40	0.79	12.0	2.69	4.49	12.1	2.3	Lot (80% Impervious Max.)	POND A
A4	3.70	0.79	12.0	2.92	4.49	13.1	2.5	Lot (80% Impervious Max.)	POND A
A5	2.70	0.79	12.0	2.13	4.49	9.6	1.8	Lot (80% Impervious Max.)	POND A
A6	2.00	0.79	12.0	1.58	4.49	7.1	1.3	Lot (80% Impervious Max.)	POND A
A7	2.30	0.79	12.0	1.82	4.49	8.2	1.5	Lot (80% Impervious Max.)	POND A
A8	2.40	0.79	12.0	1.90	4.49	8.5	1.6	Lot (80% Impervious Max.)	POND A
A9	1.70	0.79	12.0	1.34	4.49	6.0	1.1	Lot (80% Impervious Max.)	POND A
A10	2.70	0.79	12.0	2.13	4.49	9.6	1.8	Lot (80% Impervious Max.)	POND A
A11	2.60	0.79	12.0	2.05	4.49	9.2	1.7	Lot (80% Impervious Max.)	POND A
A12	2.70	0.79	12.0	2.13	4.49	9.6	1.8	Lot (80% Impervious Max.)	POND A
A13	3.10	0.79	12.0	2.45	4.49	11.0	2.1	Lot (80% Impervious Max.)	POND A
A14	2.70	0.79	12.0	2.13	4.49	9.6	1.8	Lot (80% Impervious Max.)	POND A
A15	2.20	0.79	12.0	1.74	4.49	7.8	1.5	Lot (80% Impervious Max.)	POND A
A16	2.60	0.79	12.0	2.05	4.49	9.2	1.7	Lot (80% Impervious Max.)	POND A
A17	2.40	0.79	12.0	1.90	4.49	8.5	1.6	Lot (80% Impervious Max.)	POND A
A18	2.30	0.79	12.0	1.82	4.49	8.2	1.5	Lot (80% Impervious Max.)	POND A
A19	2.30	0.79	12.0	1.82	4.49	8.2	1.5	Lot (80% Impervious Max.)	POND A
A20	0.70	0.79	12.0	0.55	4.49	2.5	0.5	Lot (80% Impervious Max.)	POND A
A21	1.80	0.79	12.0	1.42	4.49	6.4	1.2	Lot (80% Impervious Max.)	POND A
A22	1.80	0.79	12.0	1.42	4.49	6.4	1.2	Lot (80% Impervious Max.)	POND A
A23	1.80	0.79	12.0	1.42	4.49	6.4	1.2	Lot (80% Impervious Max.)	POND A
A24	1.80	0.79	12.0	1.42	4.49	6.4	1.2	Lot (80% Impervious Max.)	POND A
A25	4.30	0.35	12.0	1.51	4.49	6.8	2.9	HYDROMODIFICATION BASIN - POND A	POND A
A26	1.90	0.58	12.0	1.10	4.49	5.0	1.3	DG Access Road	POND A
A27	1.50	0.35	39.3	0.53	2.09	1.1	1.1	Offsite	BYPASS
A-ST1	24.30	0.85	12.0	20.66	4.49	92.8	16.2	Streets	POND A
A-OS1	135.70	0.35	39.3	47.50	2.09	99.3	99.3	Offsite Run-on	BYPASS
A-OS2	72.70	0.35	39.3	25.45	2.09	53.2	53.2	Offsite Run-on	BYPASS
A-OS3	17.30	0.35	39.3	6.06	2.09	12.7	12.7	Offsite Run-on	BYPASS
A-OS4	2.50	0.35	39.3	0.88	2.09	1.8	1.8	Offsite Run-on	BYPASS
BASIN A Area=	317.1	0.47		148.6		Q ₁₀₀ = 474.7	226.4	MAX. ALLOWABLE RELEASE RATE: 226.37 CFS	

NOTE: A PRE-PROJECT TIME OF CONCENTRATION IS APPLIED TO THE UNDETAINED (UNDEVELOPED) BASINS SINCE THE PROPOSED DECREASE IN TIME OF CONCENTRATION WILL BE MITIGATED FOR BY REGIONAL AND ONLOT DETENTION FACILITIES.

UNDETAINED BASINS	AREA ac.	Q100 cfs
A26	1.5	1.1
A-OS1	135.7	99.3
A-OS2	72.7	53.2
A-OS3	17.3	12.7
A-OS4	2.5	1.8
TOTAL:	229.7	168.1

BASIN A MAX. ALLOWABLE Q₁₀₀ (PRE-PROJECT Q₁₀₀): 226.37
 SUBTRACT UNDETAINED Q₁₀₀: -168.1
 POND A MAX. OUTFLOW Q₁₀₀: 58.3

POND A TRIBUTARY AREA: 87.4
 POND A TRIBUTARY AREA, AVE. C: 0.78
 POND A INFLOW: 306.5

OTAY BUSINESS PARK - PROPOSED CONDITION**POST-PROJECT HYDROLOGY - BASIN B (EAST)***(Rational Method Procedure)*

Otay Mesa, CA		DESIGN STORM		100 YR		RUN:		1/30/14 4:31 PM	
P6= 3.0									
BASIN INFORMATION									
DRAINAGE BASIN	AREA ac.	RUNOFF COEFF	T _c min	C x A	I ₁₀₀ in/hr	Undetained Q ₁₀₀ cfs	Approx. Detained Q ₁₀₀ cfs	REMARKS	TRIBUTARY TO
B1	1.90	0.79	8.0	1.50	5.84	8.8	0.7	Lot (80% Impervious Max.)	POND B
B2	2.20	0.79	8.0	1.74	5.84	10.1	0.8	Lot (80% Impervious Max.)	POND B
B3	5.70	0.79	8.0	4.50	5.84	26.3	2.0	Lot (80% Impervious Max.)	POND B
B4	4.30	0.79	8.0	3.40	5.84	19.8	1.5	Lot (80% Impervious Max.)	POND B
B5	4.80	0.79	8.0	3.79	5.84	22.1	1.7	Lot (80% Impervious Max.)	POND B
B6	4.30	0.79	8.0	3.40	5.84	19.8	1.5	Lot (80% Impervious Max.)	POND B
B7	4.00	0.79	8.0	3.16	5.84	18.4	1.4	Lot (80% Impervious Max.)	POND B
B8	1.30	0.35	8.0	0.46	5.84	2.7	0.5	Lot (80% Impervious Max.)	POND B
B9	1.30	0.79	8.0	1.03	5.84	6.0	0.5	Lot (80% Impervious Max.)	POND B
B10	2.60	0.79	8.0	2.05	5.84	12.0	0.9	Lot (80% Impervious Max.)	POND B
B11	3.30	0.79	8.0	2.61	5.84	15.2	1.2	Lot (80% Impervious Max.)	POND B
B12	46.60	0.35	39.3	16.31	2.09	34.1	34.1	Offsite	BYPASS
B-ST1	1.70	0.85	8.0	1.45	5.84	8.4	0.6	Streets	POND B
B-ST2	1.10	0.85	8.0	0.94	5.84	5.5	0.4	Streets	POND B
B-OS1	628.70	0.35	39.3	220.05	2.09	459.9	459.9	Offsite Run-on	BYPASS
BASIN A Area=		713.8	0.37	266.4	Q ₁₀₀ =	669.2	507.7	MAX. ALLOWABLE RELEASE RATE: 507.73 CFS	

NOTE: A PRE-PROJECT TIME OF CONCENTRATION IS APPLIED TO THE UNDETAINED (UNDEVELOPED) BASINS SINCE THE PROPOSED DECREASE IN TIME OF CONCENTRATION WILL BE MITIGATED FOR BY REGIONAL AND ONLOT DETENTION FACILITIES.

UNDETAINED BASINS	AREA ac.	Q ₁₀₀ cfs
B12	46.6	34.1
B-OS1	628.7	459.9
TOTAL:	675.3	494.0

BASIN B MAX. ALLOWABLE Q₁₀₀ (PRE-PROJECT Q₁₀₀): 507.73
 SUBTRACT UNDETAINED Q₁₀₀: -494.0
 POND B MAX. OUTFLOW Q₁₀₀: 13.7

POND B TRIBUTARY AREA: 38.5
 POND B TRIBUTARY AREA, AVE. C: 0.78
 POND B INFLOW: 175.2

Addendum to Drainage Study for :
Otay Business Park, TM 5505, Otay Mesa, CA

DETENTION ROUTING

Hydrograph Report

Hydraflow Hydrographs by Intelisolve v9.23

Thursday, Jan 30, 2014

Hyd. No. 2

POND A (WEST) - 100YR

Hydrograph type = Reservoir

Storm frequency = 100 yrs

Time interval = 12 min

Inflow hyd. No. = 1 - POND A (WEST) - 100YR INFLOW

Reservoir name = POND A (WEST)

Peak discharge = 10.90 cfs ~~←~~ MAX. 100YR
OUTFLOW

Time to peak = 6.00 hrs

Hyd. volume = 736,319 cuft = *58.3 CFS*


Max. Elevation ↗ = 500.53 ft

$$\text{Max. Storage} = 665,208 \text{ cuft}$$

Storage Indication method used.

ANTICIPATED —
TOP OF POND.
~ 503 FT

$$FB = 503 - 500.53 = \underline{2.47 \text{ FT}}$$



Pond Report

2

Hydraflow Hydrographs by Intelisolve v9.23

Thursday, Jan 30, 2014

Pond No. 1 - POND A (WEST)

Pond Data

Contours - User-defined contour areas. Conic method used for volume calculation. Beginning Elevation = 496.00 ft

Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	496.00	137,150	0	0
1.00	497.00	141,440	139,276	139,276
2.00	498.00	145,750	143,575	282,851
3.00	499.00	150,100	147,905	430,756
4.00	500.00	154,500	152,280	583,035
5.00	501.00	158,900	156,679	739,714
6.00	502.00	163,300	161,079	900,793

MIN. STORAGE FOR
HYDROMODIFICATION = 734,350 CF

Culvert / Orifice Structures


	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 6.00	22.00	0.00	0.00
Span (in)	= 6.00	22.00	0.00	0.00
No. Barrels	= 1	1	0	0
Invert El. (ft)	= 496.00	499.10	0.00	0.00
Length (ft)	= 0.50	0.50	0.00	0.00
Slope (%)	= 0.00	0.00	0.00	n/a
N-Value	= .013	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	No	No	No

Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 9.40	0.00	0.00	0.00
Crest El. (ft)	= 500.90	0.00	0.00	0.00
Weir Coeff.	= 3.33	3.33	3.33	3.33
Weir Type	= Rect	---	---	---
Multi-Stage	= No	No	No	No
Exfil. (in/hr)	= 0.000 (by Contour)			
TW Elev. (ft)	= 0.00			

OUTLET
SIZING/ELEVATIONS
PER
HYDROMODIFICATION
CALCULATIONS,
SEE SWMP

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).



Hydrograph Report

Hydraflow Hydrographs by Intelisolve v9.23

Thursday, Jan 30, 2014

Hyd. No. 2

POND A (WEST) - 100YR

Hydrograph type = Reservoir

Storm frequency = 100 yrs

Time interval = 12 min

Inflow hyd. No. = 1 - POND A (WEST) - 100YR INFLOW

Reservoir name = POND A (WEST)

Peak discharge = 10.90 cfs

Time to peak = 6.00 hrs

Hyd. volume = 736,319 cuft


Max. Elevation = 500.53 ft

Max. Storage = 665,208 cuft

Storage Indication method used.

POND A (WEST) - 100YR

Hyd. No. 2 -- 100 Year



RUN DATE 1/30/2014
HYDROGRAPH FILE NAME Text1
TIME OF CONCENTRATION 12 MIN.
6 HOUR RAINFALL 3 INCHES
BASIN AREA 87.4 ACRES
RUNOFF COEFFICIENT 0.78
PEAK DISCHARGE 306.5 CFS

POND A (WEST) PEAK 100YR INFLOW

TIME (MIN) = 0	DISCHARGE (CFS) = 0
TIME (MIN) = 12	DISCHARGE (CFS) = 12.3
TIME (MIN) = 24	DISCHARGE (CFS) = 12.5
TIME (MIN) = 36	DISCHARGE (CFS) = 13.1
TIME (MIN) = 48	DISCHARGE (CFS) = 13.5
TIME (MIN) = 60	DISCHARGE (CFS) = 14.2
TIME (MIN) = 72	DISCHARGE (CFS) = 14.6
TIME (MIN) = 84	DISCHARGE (CFS) = 15.5
TIME (MIN) = 96	DISCHARGE (CFS) = 16
TIME (MIN) = 108	DISCHARGE (CFS) = 17.2
TIME (MIN) = 120	DISCHARGE (CFS) = 17.8
TIME (MIN) = 132	DISCHARGE (CFS) = 19.4
TIME (MIN) = 144	DISCHARGE (CFS) = 20.3
TIME (MIN) = 156	DISCHARGE (CFS) = 22.5
TIME (MIN) = 168	DISCHARGE (CFS) = 23.9
TIME (MIN) = 180	DISCHARGE (CFS) = 27.4
TIME (MIN) = 192	DISCHARGE (CFS) = 29.7
TIME (MIN) = 204	DISCHARGE (CFS) = 36.3
TIME (MIN) = 216	DISCHARGE (CFS) = 41.3
TIME (MIN) = 228	DISCHARGE (CFS) = 60.7
TIME (MIN) = 240	DISCHARGE (CFS) = 85.3
TIME (MIN) = 252	DISCHARGE (CFS) = 306.5 ← PEAK Q ₁₀₀
TIME (MIN) = 264	DISCHARGE (CFS) = 48.7
TIME (MIN) = 276	DISCHARGE (CFS) = 32.6
TIME (MIN) = 288	DISCHARGE (CFS) = 25.5
TIME (MIN) = 300	DISCHARGE (CFS) = 21.3
TIME (MIN) = 312	DISCHARGE (CFS) = 18.6
TIME (MIN) = 324	DISCHARGE (CFS) = 16.6
TIME (MIN) = 336	DISCHARGE (CFS) = 15
TIME (MIN) = 348	DISCHARGE (CFS) = 13.8
TIME (MIN) = 360	DISCHARGE (CFS) = 12.8
TIME (MIN) = 372	DISCHARGE (CFS) = 0

Hydrograph Report

Hydraflow Hydrographs by Intelisolve v9.23

Thursday, Jan 30, 2014

Hyd. No. 4

POND B (EAST) - 100YR

Hydrograph type = Reservoir

Storm frequency = 100 yrs

Time interval = 8 min

Inflow hyd. No. = 3 - POND B (EAST) - 100YR INFLOW

Reservoir name = POND B (EAST)

Peak discharge = 0.785 cfs

Time to peak = 6.13 hrs

Hyd. volume = 324,900 cuft

Max. Elevation = 504.17 ft

Max. Storage = 314,787 cuft

MAX. 100YR

OUTFLOW
ALLOWED
= 13.7 CFS


Storage Indication method used.

ANTICIPATED
TOP OF POND
~ 508 FT

FB = 508 - 504.17 FT = 3.83 FT

POND B (EAST) - 100YR

Hyd. No. 4 -- 100 Year



Pond Report

2

Hydraflow Hydrographs by Intelisolve v9.23

Thursday, Jan 30, 2014

Pond No. 2 - POND B (EAST)

Pond Data

Contours - User-defined contour areas. Conic method used for volume calculation. Beginning Elevation = 493.00 ft

Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	493.00	20,780	0	0
1.00	494.00	22,000	21,385	21,385
2.00	495.00	23,270	22,630	44,015
3.00	496.00	24,560	23,910	67,924
4.00	497.00	25,880	25,215	93,139
5.00	498.00	27,230	26,549	119,689
6.00	499.00	28,620	27,919	147,608
7.00	500.00	30,030	29,319	176,927
8.00	501.00	31,470	30,744	207,671
9.00	502.00	32,950	32,204	239,875
10.00	503.00	34,460	33,699	273,574
11.00	504.00	36,000	35,224	308,798
12.00	505.00	37,580	36,784	345,581
13.00	506.00	39,185	38,376	383,957
14.00	507.00	40,720	39,946	423,903
15.00	508.00	42,360	41,533	465,436

MIN. STORAGE @ 14 FT
FOR HYDROMODIFICATION
= 293,350 CF

Culvert / Orifice Structures


	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 3.00	16.00	0.00	0.00
Span (in)	= 3.00	16.00	0.00	0.00
No. Barrels	= 1	1	0	0
Invert El. (ft)	= 493.00	504.65	0.00	0.00
Length (ft)	= 0.50	0.50	0.00	0.00
Slope (%)	= 0.00	0.00	0.00	n/a
N-Value	= .013	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	No	No	No

Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 9.40	0.00	0.00	0.00
Crest El. (ft)	= 506.00	0.00	0.00	0.00
Weir Coeff.	= 3.33	3.33	3.33	3.33
Weir Type	= Rect	---	---	---
Multi-Stage	= No	No	No	No
Exfil.(in/hr)	= 0.000 (by Contour)			
TW Elev. (ft)	= 0.00			

OUTLET
SIZING/ELEVATIONS
PER
HYDROMODIFICATION
CALCULATIONS
SEE SWMP

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).



Hydrograph Report

Hydraflow Hydrographs by Intelisolve v9.23

Thursday, Jan 30, 2014

Hyd. No. 4

POND B (EAST) - 100YR

Hydrograph type = Reservoir

Storm frequency = 100 yrs

Time interval = 8 min

Inflow hyd. No. = 3 - POND B (EAST) - 100YR INFLOW

Reservoir name = POND B (EAST)

Peak discharge = 0.785 cfs

Time to peak = 6.13 hrs

Hyd. volume = 324,900 cuft


Max. Elevation = 504.17 ft

Max. Storage = 314,787 cuft

Storage Indication method used.

POND B (EAST) - 100YR

Hyd. No. 4 -- 100 Year



RUN DATE 1/30/2014
HYDROGRAPH FILE NAME Text1
TIME OF CONCENTRATION 8 MIN.
6 HOUR RAINFALL 3 INCHES
BASIN AREA 38.5 ACRES
RUNOFF COEFFICIENT 0.78
PEAK DISCHARGE 175.2 CFS

POND B (EAST) PEAK 100YR INFLOW

TIME (MIN) = 0	DISCHARGE (CFS) = 0
TIME (MIN) = 8	DISCHARGE (CFS) = 5.4
TIME (MIN) = 16	DISCHARGE (CFS) = 5.5
TIME (MIN) = 24	DISCHARGE (CFS) = 5.6
TIME (MIN) = 32	DISCHARGE (CFS) = 5.7
TIME (MIN) = 40	DISCHARGE (CFS) = 5.9
TIME (MIN) = 48	DISCHARGE (CFS) = 6
TIME (MIN) = 56	DISCHARGE (CFS) = 6.2
TIME (MIN) = 64	DISCHARGE (CFS) = 6.3
TIME (MIN) = 72	DISCHARGE (CFS) = 6.6
TIME (MIN) = 80	DISCHARGE (CFS) = 6.7
TIME (MIN) = 88	DISCHARGE (CFS) = 7
TIME (MIN) = 96	DISCHARGE (CFS) = 7.2
TIME (MIN) = 104	DISCHARGE (CFS) = 7.5
TIME (MIN) = 112	DISCHARGE (CFS) = 7.7
TIME (MIN) = 120	DISCHARGE (CFS) = 8.1
TIME (MIN) = 128	DISCHARGE (CFS) = 8.4
TIME (MIN) = 136	DISCHARGE (CFS) = 8.9
TIME (MIN) = 144	DISCHARGE (CFS) = 9.2
TIME (MIN) = 152	DISCHARGE (CFS) = 9.8
TIME (MIN) = 160	DISCHARGE (CFS) = 10.2
TIME (MIN) = 168	DISCHARGE (CFS) = 11.1
TIME (MIN) = 176	DISCHARGE (CFS) = 11.6
TIME (MIN) = 184	DISCHARGE (CFS) = 12.9
TIME (MIN) = 192	DISCHARGE (CFS) = 13.7
TIME (MIN) = 200	DISCHARGE (CFS) = 15.7
TIME (MIN) = 208	DISCHARGE (CFS) = 17
TIME (MIN) = 216	DISCHARGE (CFS) = 20.8
TIME (MIN) = 224	DISCHARGE (CFS) = 23.6
TIME (MIN) = 232	DISCHARGE (CFS) = 34.7
TIME (MIN) = 240	DISCHARGE (CFS) = 49
TIME (MIN) = 248	DISCHARGE (CFS) = 175.2 ← PEAK
TIME (MIN) = 256	DISCHARGE (CFS) = 27.8
TIME (MIN) = 264	DISCHARGE (CFS) = 18.6
TIME (MIN) = 272	DISCHARGE (CFS) = 14.6
TIME (MIN) = 280	DISCHARGE (CFS) = 12.2
TIME (MIN) = 288	DISCHARGE (CFS) = 10.6
TIME (MIN) = 296	DISCHARGE (CFS) = 9.5
TIME (MIN) = 304	DISCHARGE (CFS) = 8.6
TIME (MIN) = 312	DISCHARGE (CFS) = 7.9
TIME (MIN) = 320	DISCHARGE (CFS) = 7.3
TIME (MIN) = 328	DISCHARGE (CFS) = 6.9
TIME (MIN) = 336	DISCHARGE (CFS) = 6.5
TIME (MIN) = 344	DISCHARGE (CFS) = 6.1
TIME (MIN) = 352	DISCHARGE (CFS) = 5.8
TIME (MIN) = 360	DISCHARGE (CFS) = 5.5
TIME (MIN) = 368	DISCHARGE (CFS) = 0

SECTION 4

CHANNEL CALCULATIONS

PROPOSED CHANNEL

Consistent with TM5505, the project proposes to utilize an open channel to convey project run-on through Basin B. The location of the channel is moved to the west to both facilitate the ability to create a rough graded pad for the future Point of Entry to the east, and to also align the flow path more closely to the natural conveyance. Channel calculations, utilizing peak 100-year flow rates, are provided in this section.



LEGEND

PROPOSED GROUND CONTOURS
360

EXISTING GROUND CONTOURS
360 INDEX
360 INTERMEDIATE

DRAINAGE BASIN DESIGNATOR

A
0.57
—BASIN DESIGNATION
(ALPHA CHARACTERS DESIGNATE
REGIONAL RUNOFF AREAS)

— BASIN AREA (Acres)

DRAINAGE BASIN BOUNDARY

PROPERTY LINE

STORM DRAIN PIPE

STORM DRAIN CLEANOUT

STORM DRAIN CATCH BASIN

STORM DRAIN CURB INLET

PROPOSED STORM WATER COLLECTION
BASIN & RISER

PROPOSED OPEN DRAINAGE CHANNEL

PROPOSED HEADWALL/ENERGY DISSIPATOR

PROPOSED BROW DITCH

ROCK LINED
DROP STRUCTURE
(TYP)

NODE 140
Q100=474.7 CFS (UNDETAINED)
Q100=226.4 CFS MAX. (DETAINED)

DETENTION
POND "A"

DETENTION
POND "B"

NODE 230
Q100=669.2 CFS (UNDETAINED)
Q100=507.7 CFS MAX. (DETAINED)

Open Channel - Section A

Worksheet for Trapezoidal Channel

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth

Input Data	
Mannings Coeff	0.035
Slope	0.020000 ft/ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	30.00 ft
Discharge	494.00 cfs


Results	
Depth	1.80 ft ←
Flow Area	60.4 ft ²
Wetted Perim	38.04 ft
Top Width	37.20 ft
Critical Depth	1.95 ft
Critical Slope	0.015309 ft/ft
Velocity	8.17 ft/s ←
Velocity Head	1.04 ft
Specific Energ	2.84 ft
Froude Numb	1.13
Flow Type	supercritical

X-Sec, Open Channel - Section A

Cross Section for Trapezoidal Channel

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth

Section Data	
Mannings Coeff	0.035
Slope	0.020000 ft/ft
Depth	1.80 ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	30.00 ft
Discharge	494.00 cfs



Open Channel - Section B

Worksheet for Trapezoidal Channel

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth


Input Data	
Mannings Coeff	0.035
Slope	0.004000 ft/ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	30.00 ft
Discharge	494.00 cfs

Results	
Depth	2.87 ft ←
Flow Area	102.7 ft ²
Wetted Perim	42.85 ft
Top Width	41.49 ft
Critical Depth	1.95 ft
Critical Slope	0.015309 ft/ft
Velocity	4.81 ft/s ←
Velocity Head	0.36 ft
Specific Energ	3.23 ft
Froude Numb	0.54
Flow Type	Subcritical

X-Sec, Open Channel - Section B
Cross Section for Trapezoidal Channel

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth

Section Data	
Mannings Coeff	0.035
Slope	0.004000 ft/ft
Depth	2.87 ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	30.00 ft
Discharge	494.00 cfs



Open Channel - Section C

Worksheet for Trapezoidal Channel

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth

Input Data	
Mannings Coeff	0.035
Slope	0.014000 ft/ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	40.00 ft
Discharge	494.00 cfs


Results	
Depth	1.70 ft
Flow Area	73.6 ft ²
Wetted Perim	47.58 ft
Top Width	46.78 ft
Critical Depth	1.63 ft
Critical Slope	0.015874 ft/ft
Velocity	6.72 ft/s
Velocity Head	0.70 ft
Specific Energ	2.40 ft
Froude Numb	0.94
Flow Type	Subcritical

X-Sec, Open Channel - Section C

Cross Section for Trapezoidal Channel

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth

Section Data	
Mannings Coeff	0.035
Slope	0.014000 ft/ft
Depth	1.70 ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	40.00 ft
Discharge	494.00 cfs



Open Channel - Section D

Worksheet for Trapezoidal Channel

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth


Input Data	
Mannings Coeff	0.035
Slope	0.010000 ft/ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	40.00 ft
Discharge	494.00 cfs

Results	
Depth	1.87 ft ←
Flow Area	81.9 ft²
Wetted Perim	48.37 ft
Top Width	47.49 ft
Critical Depth	1.63 ft
Critical Slope	0.015874 ft/ft
Velocity	6.03 ft/s ←
Velocity Head	0.57 ft
Specific Energ	2.44 ft
Froude Numb	0.81
Flow Type	Subcritical

X-Sec, Open Channel - Section D **Cross Section for Trapezoidal Channel**

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth

Section Data	
Mannings Coeff	0.035
Slope	0.010000 ft/ft
Depth	1.87 ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	40.00 ft
Discharge	494.00 cfs



Open Channel - Section E

Worksheet for Trapezoidal Channel

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth


Input Data	
Mannings Coeffic	0.035
Slope	0.004000 ft/ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	40.00 ft
Discharge	494.00 cfs

Results	
Depth	2.45 ft ←
Flow Area	110.1 ft²
Wetted Perim	50.96 ft
Top Width	49.81 ft
Critical Depth	1.63 ft
Critical Slope	0.015874 ft/ft
Velocity	4.49 ft/s ←
Velocity Head	0.31 ft
Specific Energ	2.76 ft
Froude Numb	0.53
Flow Type	Subcritical

X-Sec, Open Channel - Section E
Cross Section for Trapezoidal Channel

Project Description	
Worksheet	Open Channel - Sec
Flow Element	Trapezoidal Channe
Method	Manning's Formula
Solve For	Channel Depth

Section Data	
Mannings Coeffic	0.035
Slope	0.004000 ft/ft
Depth	2.45 ft
Left Side Slope	2.00 H : V
Right Side Slope	2.00 H : V
Bottom Width	40.00 ft
Discharge	494.00 cfs



Addendum to Drainage Study for :
Otay Business Park, TM 5505, Otay Mesa, CA

SECTION 5

REFERENCE CALCULATIONS/ EXHIBITS


EXCERPTS FROM THE APPROVED DRAINAGE STUDY FOR TM5505

The following excerpts are provided for reference: Exhibit B – Existing Condition (Reduced), Exhibit C – Proposed Condition (Reduced), Pre-Project Hydrology, and Proposed Detention Routing.

Addendum to Drainage Study for :
Otay Business Park, TM 5505, Otay Mesa, CA

REFERENCE EXHIBITS

K:\SND_LDEV\095529000 - Otay Business Park\Drainage Study\Exhibits\Exhibit B - Existing Cond\529000-Existing Cond.dwg 9-20-10-11:18 PM



LEGEND

PROJECT BOUNDARY

BASE BOUNDARY

ACREAGE

NODE



NORTH

GRAPHIC SCALE



(IN FEET)

1 inch = 500 ft.



OTAY BUSINESS PARK

EXHIBIT B
EXISTING CONDITION
DRAINAGE EXHIBIT



Kimley-Horn © 2010
and Associates, Inc.

K:\SND_LDEV\095529000 - Otay Business Park\Drainage Study\Exhibits\Exhibit C - Proposed Cond\529000-Proposed Cond.dwg 9-20-10-1:14 PM



OTAY BUSINESS PARK
EXHIBIT C
PROPOSED CONDITION (1 of 2)
DRAINAGE EXHIBIT

PROJECT BOUNDARY
BASIN BOUNDARY
FLOWPATH
ACREAGE
NODE
PROPOSED RIP-RAP




EXHIBIT C
PROPOSED CONDITION (2 of 2)
DRAINAGE EXHIBIT

Addendum to Drainage Study for :
Otay Business Park, TM 5505, Otay Mesa, CA

PRE-PROJECT HYDROLOGY

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM PACKAGE
Reference: SAN DIEGO COUNTY FLOOD CONTROL DISTRICT
2003,1985,1981 HYDROLOGY MANUAL
(c) Copyright 1982-2006 Advanced Engineering Software (aes)
Ver. 2.0 Release Date: 06/01/2005 License ID 1499

Analysis prepared by:

Kimley-Horn & Associates, Inc
401 B Street Suite 600
San Diego, CA 92101
619-234-9411

***** DESCRIPTION OF STUDY *****
* Otay Business Park *
* Existing 100 Year Storm *
* 6/23/2009 KDC *

FILE NAME: 100.DAT
TIME/DATE OF STUDY: 11:14 04/19/2010

USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:

2003 SAN DIEGO MANUAL CRITERIA

USER SPECIFIED STORM EVENT(YEAR) = 100.00
6-HOUR DURATION PRECIPITATION (INCHES) = 3.000
SPECIFIED MINIMUM PIPE SIZE(INCH) = 18.00
SPECIFIED PERCENT OF GRADIENTS(DECIMAL) TO USE FOR FRICTION SLOPE = 0.95
SPECIFIED CONSTANT RUNOFF COEFFICIENT = 0.350
NOTE: USE MODIFIED RATIONAL METHOD PROCEDURES FOR CONFLUENCE ANALYSIS
USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL
HALF- CROWN TO STREET-CROSSFALL: CURB GUTTER-GEOMETRIES: MANNING
WIDTH CROSSFALL IN- / OUT-/PARK- HEIGHT WIDTH LIP HIKE FACTOR
NO. (FT) (FT) SIDE / SIDE/ WAY (FT) (FT) (FT) (FT) (n)
=====

1	30.0	20.0	0.018/0.018/0.020	0.67	2.00	0.0313	0.167	0.0150
---	------	------	-------------------	------	------	--------	-------	--------

=====

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:
1. Relative Flow-Depth = 0.00 FEET
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
2. (Depth)*(Velocity) Constraint = 6.0 (FT*FT/S)
*SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*

FLOW PROCESS FROM NODE 100.00 TO NODE 110.00 IS CODE = 21

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====

*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 100.00
UPSTREAM ELEVATION(FEET) = 655.00
DOWNSTREAM ELEVATION(FEET) = 650.00
ELEVATION DIFFERENCE(FEET) = 5.00
SUBAREA OVERLAND TIME OF FLOW(MIN.) = 7.490
WARNING: INITIAL SUBAREA FLOW PATH LENGTH IS GREATER THAN
THE MAXIMUM OVERLAND FLOW LENGTH = 90.00
(Reference: Table 3-1B of Hydrology Manual)
THE MAXIMUM OVERLAND FLOW LENGTH IS USED IN Tc CALCULATION!
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 6.090
SUBAREA RUNOFF(CFS) = 0.32
TOTAL AREA(ACRES) = 0.15 TOTAL RUNOFF(CFS) = 0.32

```

FLOW PROCESS FROM NODE      110.00 TO NODE      120.00 IS CODE = 52
-----
>>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<<
>>>>>TRAVELTIME THRU SUBAREA<<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =      640.00 DOWNSTREAM(FEET) =      525.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 3950.00 CHANNEL SLOPE = 0.0291
NOTE: CHANNEL FLOW OF 1. CFS WAS ASSUMED IN VELOCITY ESTIMATION
CHANNEL FLOW THRU SUBAREA(CFS) =          0.32
FLOW VELOCITY(FEET/SEC) = 2.56 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) = 25.72 Tc(MIN.) = 33.21
LONGEST FLOWPATH FROM NODE      100.00 TO NODE      120.00 =      4050.00 FEET.

*****
FLOW PROCESS FROM NODE      120.00 TO NODE      120.00 IS CODE = 81
-----
>>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 2.331
*USER SPECIFIED(GLOBAL):
NATURAL DESERT LANDSCAPING RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.3500
SUBAREA AREA(ACRES) = 99.00 SUBAREA RUNOFF(CFS) = 80.75
TOTAL AREA(ACRES) = 99.2 TOTAL RUNOFF(CFS) = 80.88
TC(MIN.) = 33.21

*****
FLOW PROCESS FROM NODE      120.00 TO NODE      130.00 IS CODE = 52
-----
>>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<<
>>>>>TRAVELTIME THRU SUBAREA<<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =      525.00 DOWNSTREAM(FEET) =      516.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 1000.00 CHANNEL SLOPE = 0.0090
CHANNEL FLOW THRU SUBAREA(CFS) =      80.88
FLOW VELOCITY(FEET/SEC) = 4.23 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) = 3.94 Tc(MIN.) = 37.16
LONGEST FLOWPATH FROM NODE      100.00 TO NODE      130.00 =      5050.00 FEET.

*****
FLOW PROCESS FROM NODE      130.00 TO NODE      130.00 IS CODE = 1
-----
>>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
TIME OF CONCENTRATION(MIN.) = 37.16
RAINFALL INTENSITY(INCH/HR) = 2.17
TOTAL STREAM AREA(ACRES) = 99.15
PEAK FLOW RATE(CFS) AT CONFLUENCE = 80.88

*****
FLOW PROCESS FROM NODE      150.00 TO NODE      160.00 IS CODE = 21
-----
>>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====
*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 100.00
UPSTREAM ELEVATION(FEET) = 638.00
DOWNSTREAM ELEVATION(FEET) = 632.00
ELEVATION DIFFERENCE(FEET) = 6.00
SUBAREA OVERLAND TIME OF FLOW(MIN.) = 7.126
WARNING: INITIAL SUBAREA FLOW PATH LENGTH IS GREATER THAN
THE MAXIMUM OVERLAND FLOW LENGTH = 92.00
(Reference: Table 3-1B of Hydrology Manual)
THE MAXIMUM OVERLAND FLOW LENGTH IS USED IN Tc CALCULATION!
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 6.289
SUBAREA RUNOFF(CFS) = 0.22

```

```

TOTAL AREA(ACRES) =      0.10  TOTAL RUNOFF(CFS) =      0.22

*****
FLOW PROCESS FROM NODE      160.00 TO NODE      170.00 IS CODE = 52
-----
>>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<<
>>>>>TRAVELTIME THRU SUBAREA<<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =      632.00  DOWNSTREAM(FEET) =      530.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 3730.00  CHANNEL SLOPE = 0.0273
NOTE: CHANNEL FLOW OF 1. CFS WAS ASSUMED IN VELOCITY ESTIMATION
CHANNEL FLOW THRU SUBAREA(CFS) =      0.22
FLOW VELOCITY(FEET/SEC) = 2.48 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) = 25.06  Tc(MIN.) = 32.19
LONGEST FLOWPATH FROM NODE      150.00 TO NODE      170.00 =      3830.00 FEET.

*****
FLOW PROCESS FROM NODE      170.00 TO NODE      170.00 IS CODE = 81
-----
>>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 2.378
*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.3500
SUBAREA AREA(ACRES) = 132.40  SUBAREA RUNOFF(CFS) = 110.20
TOTAL AREA(ACRES) = 132.5  TOTAL RUNOFF(CFS) = 110.28
TC(MIN.) = 32.19

*****
FLOW PROCESS FROM NODE      170.00 TO NODE      130.00 IS CODE = 52
-----
>>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<<
>>>>>TRAVELTIME THRU SUBAREA<<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =      530.00  DOWNSTREAM(FEET) =      516.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 1700.00  CHANNEL SLOPE = 0.0082
CHANNEL FLOW THRU SUBAREA(CFS) = 110.28
FLOW VELOCITY(FEET/SEC) = 4.44 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) = 6.39  Tc(MIN.) = 38.58
LONGEST FLOWPATH FROM NODE      150.00 TO NODE      130.00 =      5530.00 FEET.

*****
FLOW PROCESS FROM NODE      130.00 TO NODE      130.00 IS CODE = 1
-----
>>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
>>>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
TIME OF CONCENTRATION(MIN.) = 38.58
RAINFALL INTENSITY(INCH/HR) = 2.12
TOTAL STREAM AREA(ACRES) = 132.50
PEAK FLOW RATE(CFS) AT CONFLUENCE = 110.28

** CONFLUENCE DATA **
STREAM      RUNOFF      Tc      INTENSITY      AREA
NUMBER      (CFS)      (MIN.)      (INCH/HOUR)      (ACRE)
1          80.88      37.16      2.168          99.15
2         110.28      38.58      2.116         132.50

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **
STREAM      RUNOFF      Tc      INTENSITY
NUMBER      (CFS)      (MIN.)      (INCH/HOUR)
1          187.10      37.16      2.168
2          189.23      38.58      2.116

```


COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:

PEAK FLOW RATE(CFS) = 189.23 Tc(MIN.) = 38.58
TOTAL AREA(ACRES) = 231.6
LONGEST FLOWPATH FROM NODE 150.00 TO NODE 130.00 = 5530.00 FEET.

FLOW PROCESS FROM NODE 130.00 TO NODE 140.00 IS CODE = 52

>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<
>>>>TRAVELTIME THRU SUBAREA<<<<
=====

ELEVATION DATA: UPSTREAM(FEET) = 516.00 DOWNSTREAM(FEET) = 495.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 500.00 CHANNEL SLOPE = 0.0420
CHANNEL FLOW THRU SUBAREA(CFS) = 189.23
FLOW VELOCITY(FEET/SEC) = 11.81 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) = 0.71 Tc(MIN.) = 39.28
LONGEST FLOWPATH FROM NODE 150.00 TO NODE 140.00 = 6030.00 FEET.

FLOW PROCESS FROM NODE 140.00 TO NODE 140.00 IS CODE = 81

>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====

100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 2.091
*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.3500
SUBAREA AREA(ACRES) = 77.60 SUBAREA RUNOFF(CFS) = 56.80
TOTAL AREA(ACRES) = 309.2 TOTAL RUNOFF(CFS) = 226.37
TC(MIN.) = 39.28

FLOW PROCESS FROM NODE 140.00 TO NODE 140.00 IS CODE = 13

>>>>CLEAR THE MAIN-STREAM MEMORY<<<<
=====

FLOW PROCESS FROM NODE 190.00 TO NODE 200.00 IS CODE = 21

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====

*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 100.00
UPSTREAM ELEVATION(FEET) = 1560.00
DOWNSTREAM ELEVATION(FEET) = 1520.00
ELEVATION DIFFERENCE(FEET) = 40.00
SUBAREA OVERLAND TIME OF FLOW(MIN.) = 6.267
WARNING: THE MAXIMUM OVERLAND FLOW SLOPE, 10.%, IS USED IN Tc CALCULATION!
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 6.833
SUBAREA RUNOFF(CFS) = 0.24
TOTAL AREA(ACRES) = 0.10 TOTAL RUNOFF(CFS) = 0.24

FLOW PROCESS FROM NODE 200.00 TO NODE 201.00 IS CODE = 52

>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<
>>>>TRAVELTIME THRU SUBAREA<<<<
=====

ELEVATION DATA: UPSTREAM(FEET) = 1520.00 DOWNSTREAM(FEET) = 800.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 4000.00 CHANNEL SLOPE = 0.1800
NOTE: CHANNEL FLOW OF 1. CFS WAS ASSUMED IN VELOCITY ESTIMATION
NOTE: CHANNEL SLOPE OF .1 WAS ASSUMED IN VELOCITY ESTIMATION
CHANNEL FLOW THRU SUBAREA(CFS) = 0.24
FLOW VELOCITY(FEET/SEC) = 4.74 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) = 14.05 Tc(MIN.) = 20.32
LONGEST FLOWPATH FROM NODE 190.00 TO NODE 201.00 = 4100.00 FEET.

PRE-PROJECT
BASIN A (WEST)

```

*****
FLOW PROCESS FROM NODE      201.00 TO NODE      201.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  3.199
*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) =  0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.3500
SUBAREA AREA(ACRES) =  110.20  SUBAREA RUNOFF(CFS) =  123.40
TOTAL AREA(ACRES) =  110.3  TOTAL RUNOFF(CFS) =  123.51
TC(MIN.) =  20.32

*****
FLOW PROCESS FROM NODE      201.00 TO NODE      210.00 IS CODE =  52
-----
>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<
>>>>TRAVELTIME THRU SUBAREA<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =  800.00  DOWNSTREAM(FEET) =  620.00
CHANNEL LENGTH THRU SUBAREA(FEET) =  4000.00  CHANNEL SLOPE =  0.0450
CHANNEL FLOW THRU SUBAREA(CFS) =  123.51
FLOW VELOCITY(FEET/SEC) =  10.73 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) =  6.21  Tc(MIN.) =  26.53
LONGEST FLOWPATH FROM NODE      190.00 TO NODE      210.00 =  8100.00 FEET.

*****
FLOW PROCESS FROM NODE      210.00 TO NODE      210.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  2.694
*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) =  0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.3500
SUBAREA AREA(ACRES) =  386.70  SUBAREA RUNOFF(CFS) =  364.58
TOTAL AREA(ACRES) =  497.0  TOTAL RUNOFF(CFS) =  468.57
TC(MIN.) =  26.53

*****
FLOW PROCESS FROM NODE      210.00 TO NODE      220.00 IS CODE =  52
-----
>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<
>>>>TRAVELTIME THRU SUBAREA<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =  620.00  DOWNSTREAM(FEET) =  530.00
CHANNEL LENGTH THRU SUBAREA(FEET) =  4900.00  CHANNEL SLOPE =  0.0184
CHANNEL FLOW THRU SUBAREA(CFS) =  468.57
FLOW VELOCITY(FEET/SEC) =  10.39 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) =  7.86  Tc(MIN.) =  34.39
LONGEST FLOWPATH FROM NODE      190.00 TO NODE      220.00 =  13000.00 FEET.

*****
FLOW PROCESS FROM NODE      220.00 TO NODE      220.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  2.279
*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) =  0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.3500
SUBAREA AREA(ACRES) =  128.20  SUBAREA RUNOFF(CFS) =  102.25
TOTAL AREA(ACRES) =  625.2  TOTAL RUNOFF(CFS) =  498.63
TC(MIN.) =  34.39

*****
FLOW PROCESS FROM NODE      220.00 TO NODE      230.00 IS CODE =  52
-----

```

```

>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<
>>>>TRAVELTIME THRU SUBAREA<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 530.00 DOWNSTREAM(FEET) = 485.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 2890.00 CHANNEL SLOPE = 0.0156
CHANNEL FLOW THRU SUBAREA(CFS) = 498.63
FLOW VELOCITY(FEET/SEC) = 9.76 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) = 4.93 Tc(MIN.) = 39.32
LONGEST FLOWPATH FROM NODE 190.00 TO NODE 230.00 = 15890.00 FEET.

*****
FLOW PROCESS FROM NODE 230.00 TO NODE 230.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 2.090
*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.3500
SUBAREA AREA(ACRES) = 68.90 SUBAREA RUNOFF(CFS) = 50.40
TOTAL AREA(ACRES) = 694.1 TOTAL RUNOFF(CFS) = 507.73
TC(MIN.) = 39.32

*****
FLOW PROCESS FROM NODE 0.00 TO NODE 0.00 IS CODE = 13
-----
>>>>CLEAR THE MAIN-STREAM MEMORY<<<<
=====

*****
FLOW PROCESS FROM NODE 310.00 TO NODE 315.00 IS CODE = 21
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 100.00
UPSTREAM ELEVATION(FEET) = 572.00
DOWNSTREAM ELEVATION(FEET) = 562.00
ELEVATION DIFFERENCE(FEET) = 10.00
SUBAREA OVERLAND TIME OF FLOW(MIN.) = 6.267
WARNING: THE MAXIMUM OVERLAND FLOW SLOPE, 10.%, IS USED IN Tc CALCULATION!
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 6.833
SUBAREA RUNOFF(CFS) = 0.24
TOTAL AREA(ACRES) = 0.10 TOTAL RUNOFF(CFS) = 0.24

*****
FLOW PROCESS FROM NODE 315.00 TO NODE 320.00 IS CODE = 52
-----
>>>>COMPUTE NATURAL VALLEY CHANNEL FLOW<<<<
>>>>TRAVELTIME THRU SUBAREA<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 562.00 DOWNSTREAM(FEET) = 506.00
CHANNEL LENGTH THRU SUBAREA(FEET) = 2000.00 CHANNEL SLOPE = 0.0280
NOTE: CHANNEL FLOW OF 1. CFS WAS ASSUMED IN VELOCITY ESTIMATION
CHANNEL FLOW THRU SUBAREA(CFS) = 0.24
FLOW VELOCITY(FEET/SEC) = 2.51 (PER LACFCD/RCFC&WCD HYDROLOGY MANUAL)
TRAVEL TIME(MIN.) = 13.28 Tc(MIN.) = 19.55
LONGEST FLOWPATH FROM NODE 310.00 TO NODE 320.00 = 2100.00 FEET.

*****
FLOW PROCESS FROM NODE 320.00 TO NODE 320.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 3.281
*USER SPECIFIED(GLOBAL):
GENERAL INDUSTRIAL RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0

```

PRE-PROJECT
 BASIN B (EAST)
 OUTFLOW

AREA-AVERAGE RUNOFF COEFFICIENT = 0.3500
SUBAREA AREA(ACRES) = 15.60 SUBAREA RUNOFF(CFS) = 17.91
TOTAL AREA(ACRES) = 15.7 TOTAL RUNOFF(CFS) = 18.03
TC(MIN.) = 19.55

=====

END OF STUDY SUMMARY:

TOTAL AREA(ACRES) = 15.7 TC(MIN.) = 19.55
PEAK FLOW RATE(CFS) = 18.03

=====

END OF RATIONAL METHOD ANALYSIS

Addendum to Drainage Study for :
Otay Business Park, TM 5505, Otay Mesa, CA

DETENTION ROUTING

Hydrograph Plot

Hydraflow Hydrographs by Intelisolve

Tuesday, Jun 23 2009, 3:40 PM

Hyd. No. 2


west basin detained

Hydrograph type = Reservoir
 Storm frequency = 100 yrs
 Inflow hyd. No. = 1
 Reservoir name = Basin A (S.W. corner)

Peak discharge = 1.41 cfs
 Time interval = 12 min
 Max. Elevation = 501.11 ft
 Max. Storage = 847,387 cuft


Storage Indication method used.

Hydrograph Volume = 863,234 cuft



Pond No. 1 - Basin A (S.W. corner)

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2009 by Autodesk, Inc. v6.066



Front View
NTS - Looking Downstream

Inflow hydrograph = 1. Manual - west basin

Hydrograph Plot

Hydraflow Hydrographs by Intelisolve

Tuesday, Jun 23 2009, 3:28 PM

Hyd. No. 2


<no description>

Hydrograph type = Reservoir
 Storm frequency = 100 yrs
 Inflow hyd. No. = 1
 Reservoir name = Basin B (S.E. corner)

Peak discharge = 1.53 cfs
 Time interval = 8 min
 Max. Elevation = 498.96 ft
 Max. Storage = 671,456 cuft


Storage Indication method used.

Hydrograph Volume = 688,896 cuft



Pond No. 2 - Basin B (S.E. corner)

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2009 by Autodesk, Inc. v6.066




Inflow hydrograph = 1. Manual - East Basin

Addendum to Drainage Study for :
Otay Business Park, TM 5505, Otay Mesa, CA

SECTION 6

DRAINAGE EXHIBIT



LEGEND

PROPOSED GROUND CONTOURS
360

EXISTING GROUND CONTOURS
360 INDEX
360 INTERMEDIATE

DRAINAGE BASIN DESIGNATOR

A
0.57 —BASIN DESIGNATION
(ALPHA CHARACTERS DESIGNATE
REGIONAL RUNOFF AREAS)

— BASIN AREA (Acres)

DRAINAGE BASIN BOUNDARY

PROPERTY LINE

STORM DRAIN PIPE

STORM DRAIN CLEANOUT

STORM DRAIN CATCH BASIN

STORM DRAIN CURB INLET

PROPOSED STORM WATER COLLECTION
BASIN & RISER

PROPOSED OPEN DRAINAGE CHANNEL

PROPOSED HEADWALL/ENERGY DISSIPATOR

PROPOSED BROW DITCH

NODE 140
Q100=474.7 CFS (UNDETAILED)
Q100=226.4 CFS MAX. (DETAINED)

DETENTION
POND "A"

DETENTION
POND "B"

NODE 230
Q100=669.2 CFS (UNDETAILED)
Q100=507.7 CFS MAX. (DETAINED)

0 100 200 400 600
SCALE: 1" = 200'